CONSTRUCTION PLANS FOR

CITY OF SEGUIN

BS 123 12" WATER MAIN LOOP

PHASE II AND III

IN THE CITY OF SEGUIN GUADALUPE COUNTY, TEXAS AUGUST 2014

CLIENT:



205 N. RIVER ST PO BOX 591 SEGUIN, TEXAS 78156 (830) 401–2776 ATTN: JOE RAMOS, P.E., CITY ENGINEER

ENGINEER:

ktotz (1) associates

7550 IH-10 WEST NORTHWEST CENTER, SUITE 300 SAN ANTONIO, TEXAS 78229 T 210.736.0425 F 210.736.0405 SANANTONIO.OFFICE@KLOTZ.COM TEXAS PE FIRM REG. # F-929

SURVEYOR:

BETTERSWORTH & ASSOCIATES, INC.


111 E. MOUNTAIN STREET SEGUIN, TEXAS 78155 (830) 379-5552

GEOTECHNICAL:

Frost GeoSciences

13402 WESTERN OAK HELOTES, TEXAS 78023 (210) 372-1315

PROJECT NO: FGS-G09133



VICINITY MAP

N.T.S.

SHEET INDEX:

- CO.O COVER SHEET
- C1.0 GENERAL NOTES
- C2.0 12" WATER MAIN QUANTITIES
- C3.0 OVERALL PROJECT LAYOUT
- C4.0 TRAFFIC CONTROL PLAN CONVENTIONAL ROAD SHOULDER WORK TCP(2-1)-12
- C5.0 TRAFFIC CONTROL PLAN CONVENTIONAL ROAD SHOULDER WORK TCP(2-2)-12
- C6.0 TEMPORARY EROSION SEDIMENT AND WATER POLLUTION CONTROL MEASURES

 EC(1)-09
- C7.0 TEMPORARY EROSION SEDIMENT AND WATER POLLUTION CONTROL MEASURES EC(3)-93
- C8.0 TEMPORARY EROSION SEDIMENT AND WATER POLLUTION CONTROL MEASURES
- EC(4)-93

 C9.0 TEMPORARY EROSION SEDIMENT AND WATER POLLUTION CONTROL MEASURES
- EC(5)-93
- C10.0 TEMPORARY EROSION SEDIMENT AND WATER POLLUTION CONTROL MEASURES STANDARDS 1
- C11.0 WATERLINE PLAN AND PROFILE BEGIN PROJECT TO STA 19+00.00
- C12.0 WATERLINE PLAN AND PROFILE STA 19+00.00 TO STA 28+40.00
- C13.0 WATERLINE PLAN AND PROFILE STA 28+40.00 TO STA 38+00.00 C14.0 WATERLINE PLAN AND PROFILE STA 38+00.00 TO END PROJECT
- C15.0 WATERLINE CONSTRUCTION DETAILS SHEET 1 OF 4
- C16.0 WATERLINE CONSTRUCTION DETAILS SHEET 2 OF 4
- C17.0 WATERLINE CONSTRUCTION DETAILS SHEET 3 OF 4
- C18.0 WATERLINE CONSTRUCTION DETAILS SHEET 4 OF 4



08/01/2014

- ALL CONSTRUCTION SHALL REFER TO CURRENT SAN ANTONIO WATER SYSTEM (SAWS) SPECIFICATIONS AND CITY STANDARD DETAILS UNLESS OTHERWISE SPECIFIED IN THE
- 2. ALL CONSTRUCTION SHALL ALSO REFER TO THE CITY OF SEGUIN CONSTRUCTION STANDARD SPECIFICATIONS, AND TEXAS DEPARTMENT OF TRANSPORTATION (TXDOT) WHERE APPLICABLE.
- PRIOR TO STARTING CONSTRUCTION, THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL REQUIRED PERMITS AND VERIFYING APPROVALS HAVE BEEN OBTAINED. NO CONSTRUCTION OF FABRICATION SHALL BEGIN UNTIL THE CONTRACTOR HAS RECEIVED AND THOROUGHLY REVIEWED ALL PLANS AND OTHER DOCUMENTS AS APPROVED BY ALL OF THE PERMITTING AUTHORITIES.
- 4. THE CONTRACTOR SHALL GIVE THE CITY A MINIMUM OF 48 HOURS NOTICE BEFORE
- CONTRACTOR SHALL PROTECT ALL BENCHMARKS AND PROPERTY MONUMENTATION AND SHALL REPLACE OR REPAIR AT HIS OWN EXPENSE, BENCHMARKS AND MONUMENTATION DISTURBED DURING CONSTRUCTION.
- 6. THE AMERICANS WITH DISABILITIES ACT (ADA) GUIDELINES, BOTH FEDERAL AND STATE ARE TO BE INCORPORATED IN ALL CONSTRUCTION DOCUMENTS. IF ANY CRITERIA CANNOT BE MET THEN THE ENGINEER IS TO BE ALERTED OF THE CONDITION AND INFORMED OF THE MEASURES THAT WOULD BE NECESSARY TO BE IN CONFORMANCE.
- EQUIPMENT AND MATERIALS SHALL BE STORED IN AREAS APPROVED BY THE CITY OF SEGUIN. CONSTRUCTION AND STORAGE AREAS SHALL BE KEPT NEAT AND CLEAN.
- 8. CONTRACTOR TO VERIFY THE ELEVATIONS OF ALL TIE-IN POINTS FOR INSTALLATION OF UTILITIES, CURB & GUTTER AND PAVING.
- THE CONTRACTOR SHALL NOTIFY THE ENGINEER OF ANY DISCREPANCIES BETWEEN PLAN AND FIELD CONDITIONS PROMPTLY UPON DISCOVERY. ANY CONFLICT DISCOVERED WITHIN THE CONSTRUCTION PLANS SHALL BE REPORTED IMMEDIATELY TO THE ENGINEER FOR CLARIFICATION. FAILURE TO DO SO SHALL RESULT IN CONTRACTOR'S LIABILITY FOR ISSUES ARISING FROM SUCH CONFLICTS OR
- 10. ALL VEGETATION, ROOT SYSTEMS, TOPSOIL, REFUSE AND OTHER DELETERIOUS, NON-SOIL MATERIAL SHALL BE STRIPPED FROM THE PROPOSED CONSTRUCTION AREAS. CLEAN TOPSOIL MAY BE STOCKPILED AND REUSED LATER IN LANDSCAPED
- ALL AREAS TO BE FILLED SHALL BE IN ACCORDANCE WITH GEOTECHNICAL REPORT, PROJECT NO. FGS-G09133 DATED JANUARY 8, 2010, WHICH CAN BE REVIEWED AT THE OFFICE OF ENGINEER
- ALL ROADWAY AND PAVING CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST REVISION OF THE CITY OF SEGUIN PUBLIC WORKS STANDARDS AND SPECIFICATIONS FOR CONSTRUCTION.
- 13. UPON COMPLETION OF CONSTRUCTION, THE CONTRACTOR SHALL REMOVE ALL SILT, DEBRIS AND SEDIMENT FROM THE CURB INLETS.
- 14. REPLACED CONDUITS FOR SITE LIGHTING SHALL BE INSTALLED, BACKFILLED AND PROPERLY COMPACTED PRIOR TO THE PLACEMENT OF BASE, PAVEMENT, AND CURB
- 15. THE CONTRACTOR SHALL REMOVE ALL DEBRIS, VEGETATION WHICH HAS BEEN EXCAVATED, LUMBER, CONCRETE, ETC., FROM THE CONSTRUCTION SITE AND PROPERLY DISPOSED.
- ALL EXISTING UTILITIES TO BE FIELD VERIFIED. CONTACT DIG-TESS AT 1-800-344-8377 BEFORE DIGGING.
- 17. OFF-STREET AND OFF-SITE PARKING SHALL BE PROVIDED AND MAINTAINED
- 18. NECESSARY BARRICADES, SUFFICIENT LIGHTS, SIGNS AND OTHER TRAFFIC CONTROL DEVICES AS MAY BE NECESSARY FOR THE PROTECTION AND SAFETY OF THE PUBLIC SHALL BE PROVIDED IN ACCORDANCE WITH THE TEXAS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, 2011 EDITION AND MAINTAINED WHEN WORKING IN CLOSE PROXIMITY TO PUBLIC ROADS.
- 19. BARRICADING, TRAFFIC CONTROL, AND PROJECT SIGNS SHALL CONFORM TO "STATE DEPARTMENT OF HIGHWAYS AND PUBLIC TRANSPORTATION BARRICADING AND CONSTRUCTION STANDARDS" AND THE CITY OF SEGUIN STANDARDS.
- 20. THE CONTRACTOR SHALL EXERCISE EXTREME CAUTION WHEN ENTERING MANHOLES, PIPES OR OTHER STRUCTURES SHOWN ON THE PLANS. AT A MINIMUM, THESE PIPES AND STRUCTURES SHALL BE PROPERLY VENTILATED.

TRENCH NOTES

- IN ACCORDANCE WITH THE LAWS OF THE STATE OF TEXAS AND THE U.S. OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) REGULATIONS, ALL TRENCHES OVER 5 FEET IN DEPTH IN EITHER HARD AND COMPACT OR SOFT AND UNSTABLE SOIL SHALL BE SLOPED, SHORED, SHEETED, BRACED OR OTHERWISE SUPPORTED, FURTHERMORE, ALL TRENCHES LESS THAN 5 FEET IN DEPTH SHALL ALSO BE EFFECTIVELY PROTECTED WHEN HAZARDOUS GROUND MOVEMENT MAY BE
- IN ACCORDANCE WITH THE U.S. OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION REGULATIONS, WHEN EMPLOYEES ARE EXPECTED TO BE IN TRENCHES 4 FEET DEEP OR MORE. ADEQUATE MEANS OF EXIT, SUCH AS A LADDER OR STEPS, MUST BE PROVIDED AND LOCATED SO AS TO REQUIRE NO MORE THAN 25 FEET OF LATERAL
- 3. IF DURING CONSTRUCTION IT IS FOUND THAT TRENCHES ARE IN FACT 5 FEET DEED OR MORE IN DEPTH OR TRENCHES LESS THAN 5 FEET IN DEPTH ARE IN AN AREA WHERE HAZARDOUS GROUND MOVEMENT IS EXPECTED, ALL CONSTRUCTION SHALL CEASE. THE TRENCHED AREA SHALL BE BARRICADED AND THE ENGINEER NOTIFIED IMMEDIATELY. CONSTRUCTION SHALL NOT RESUME UNTIL APPROPRIATE TRENCH SAFETY SYSTEM DETAILS ARE SUBMITTED TO AND ACCEPTED BY THE CITY OF
- 4. EXCAVATION SHALL BE PHASED SO THAT EXCAVATED AREA IS NOT OPEN FOR MORE THAN 48 HOURS. IT IS PREFERRED THAT TRENCHES BE EXCAVATED AND BACK FILLED WITHIN THE SAME DAY.

GENERAL WATER NOTES

- ALL MATERIALS AND CONSTRUCTION PROCEDURES WITHIN THE SCOPE OF CONTRACT SHALL BE APPROVED BY THE CITY OF SEGUIN AND COMPLY WITH FOLLOWING AS APPLICABLE:
- A. CURRENT TEXAS COMMISSION ON ENVIRONMENTAL QUALITY (TCEQ) FOR WATER
- B. CURRENT TXDOT "STANDARD SPECIFICATIONS FOR CONSTRUCTION OF HIGHWAYS. STREETS AND DRAINAGE.
- C. CURRENT CITY OF SEGUIN "STANDARD SPECIFICATIONS FOR CONSTRUCTION."
- D. CURRENT CITY OF SEGUIN "STANDARD SPECIFICATIONS FOR PUBLIC WORKS
- 2 THE CONTRACTOR IS TO NOTIFY AND MAKE ARRANGEMENTS WITH THE CITY OF SEGUIN UTILITIES/ PUBLIC WORKS AND THE INVOLVED HOME RESIDENTS AND/OR PROPERTY OWNERS 48 HOURS PRIOR TO EXCAVATION.
- 3. THE LOCATION AND DEPTHS OF EXISTING UTILITIES, INCLUDING SERVICE LATERALS, SHOWN ON THE PLANS ARE APPROXIMATE ONLY. ACTUAL LOCATIONS AND DEPTHS MUST BE FIELD VERIFIED BY THE CONTRACTOR AT A MINIMUM OF 500-FEET AHEAD OF THE SCHEDULED CONSTRUCTION AND IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO LOCATE UTILITY SERVICE LINES AS REQUIRED FOR CONSTRUCTION AND TO PROTECT THEM DURING CONSTRUCTION.
- 4. THE CONTRACTOR SHALL VERIFY THE EXACT LOCATION OF UNDERGROUND UTILITIES AND DRAINAGE STRUCTURES AT LEAST 48 HOURS PRIOR TO CONSTRUCTION WHETHER SHOWN ON PLANS OR NOT, AND TO PROTECT THE SAME DURING CONSTRUCTION.

CITY OF SEGUIN PUBLIC WORKS:

CITY ENGINEER 830-401-2439

UTILITY ADMINISTRATION 830-401-2776

TEXAS STATE WIDE ONE CALL LOCATOR 1-800-344-8377

TXDOT AREA OFFICE CONTACT: BRYAN ELBEL AT 830-609-0707

GUADALUPE VALLEY ELECTRICAL COOPERATIVE (GVEC) 830-401-8326

SPRING HILL WATER SUPPLY CORPORATION 830-379-7683

PETROLEUM PIPELINE 1-800-467-5686 CITGO REPRESENTATIVE MUST BE PRESENT DURING CONSTRUCTION TO ENSURE INTEGRITY OF PIPELINE AS MANDATED BY THE TEXAS RAUROAD COMMISSION. CONTACT STEPHEN SHANDLEY 210-662-0055 DURING EXCAVATION OR BORING

- 5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORING TO ITS ORIGINAL OR BETTER CONDITION FROM DAMAGES DONE TO EXISTING FENCES, CURBS, STREETS, DRIVEWAYS, SIDEWALKS, LANDSCAPING AND STRUCTURES.
- 6. THE CONTRACTOR SHALL AVOID CUTTING ROOTS LARGER THAT ONE INCH IN DIAMETER WHEN EXCAVATING NEAR EXISTING TREES, EXCAVATION IN VICINITY OF TREES SHALL PROCEED WITH CAUTION. THE CONTRACTOR SHALL CONTACT THE CITY PLANNING DEPARTMENT AT 830-401-2306 FOR GUIDANCE. CITY OF SEGUIN CONSTRUCTION INSPECTOR SHALL ALSO BE NOTIFIED.
- THE CONTRACTOR SHALL NOT PLACE ANY WASTE MATERIALS IN THE 100-YEAR FLOOD PLAIN WITHOUT FIRST OBTAINING AN APPROVED FLOOD PLAIN PERMIT.
- 8. PRIOR TO TIE-INS, ANY SHUTDOWNS OF EXISTING MAINS OF ANY SIZE MUST BE COORDINATED WITH THE CITY OF SEGUIN AT LEAST ONE WEEK OR MORE IN ADVANCE OF THE SHUTDOWN. THE CONTRACTOR MUST ALSO PROVIDE A SEQUENCE OF WORK AS RELATED TO THE TIE-INS; THIS IS AT NO ADDITIONAL COST TO THE CITY OF SEGUIN OR THE PROJECT AND IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO SEQUENCE THE WOODE ACCORDINGLY.
- 9. THE CITY OF SEGUIN SHALL MACHINE CHLORINATE NEW WATER MAINS.
- 10. THE CONTRACTOR SHALL NOT PROCEED WITH ANY PIPE INSTALLATION WORK UNTIL THEY OBTAIN A COPY OF THE APPROVED PERMIT AND HAS BEEN NOTIFIED BY THE CITY OF SEGUIN. CONSTRUCTION INSPECTION DIVISION TO PROCEED WITH THE WORK AND HAS ARRANGED A MEETING WITH THE INSPECTOR AND CONSULTANT FOR THE
- 11. NO METER BOXES TO BE SET IN DRIVEWAYS. ANY METER BOXES SET IN DRIVEWAYS

- 12. NO EXTRA-PAYMENT SHALL BE ALLOWED FOR WORK CALLED FOR ON THE PLANS BUT NOT INCLUDED ON THE BID SCHEDULE. THIS INCIDENTAL WORK WILL BE REQUIRED AND SHALL BE INCLUDED UNDER THE PAY ITEM TO WHICH IT RELATES.
- 13. CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITE(S) WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTOR'S TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES. THE CONTRACTOR'S IMPLEMENTATION OF THE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLIES WITH AS A MINIMUM, OSHA STANDARDS FOR TRENCH EXCAVATIONS. SPECIFICALLY, CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.
- 14. WORK COMPLETED BY THE CONTRACTOR WHICH HAS NOT RECEIVED A WORK ORDER OR THE NOTICE TO PROCEED FROM THE CITY OF SEGUIN INSPECTION DIVISION WILL BE SUBJECT TO REMOVAL AND REPLACEMENT BY AND AT THE EXPENSE OF THE CONTRACTOR.
- 15. THE CONTRACTOR WILL KEEP THE AREA ON TOP OF AND AROUND THE WATER METER BOX FREE OF ALL OBJECTS AND DEBRIS.
- 16. WATER SYSTEM TO BE COMPLETELY RESTRAINED. RESTRAINED LENGTH CALCULATIONS ARE FOR P.V.C. PIPE BEDDED I COMPACTED GRANULAR MATERIAL EXTENDING TO THE TOP OF THE PIPE. THE NATIVE SOIL MATERIAL IS ASSUMED TO BE INORGANIC CLAY OF HIGH PLASTICITY. DEPTH OF BURY IS ASSUMED TO BE 5 FEET.

NOTE: THESE CALCULATIONS ARE PROVIDED FOR REFERENCE. THE RESTRAINED LENGTHS SHALL BE VERIFIED BY CONTRACTOR BASED UPON THE CONDITIONS ENCOUNTERED DURING THE INSTALLATION. SEE THE SAN ANTONIO WATER SYSTEM (SAWS) SPECIFICATION BOOK AS REFERENCE.

17 THE CITY OF SEGUIN HAS ACCEPTED AND IMPLEMENTED THE SAN ANTONIO WATER SYSTEM (SAWS) SPECIFICATIONS FOR WATER AND SANITARY SEWER CONSTRUCTION.
ALL REFERENCES TO "THE CITY OF SAN ANTONIO" SHALL BE UNDERSTOOD AS "THE CITY OF SEGUIN.

UTILITY NOTES

- WATER IMPROVEMENTS SHALL FOLLOW CITY OF SEGUIN SPECIFICATIONS AND
- REQUIRED PERMITS AND APPROVALS SHALL BE OBTAINED PRIOR TO CONSTRUCTION. A FORTY—EIGHT (48) HOUR NOTICE SHALL BE GIVEN PROIR TO BEGINNING ANY WATER AND WASTEWATER CONSTRUCTION IN PUBLIC R.O.W. OR PUBLIC EASEMENT. THE CONTRACTOR SHALL NOTIFY PROPER CITY OF SEGUIN OFFICIALS FOR MAIN CONSTRUCTION, AND WATER AND WASTEWATER TAP INSPECTIONS. PRIOR TO CONSTRUCTION THE CONTRACTOR SHALL VERIFY THE LOCATIONS AND INVERTS OF ALL
- PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL VERIFY THE LOCATIONS OF ALL UTILITIES TO BE EXTENDED, TIED TO, OR ALTERED, OR SUBJECT TO DAMAGE/INCONVENIENCE BY THE CONSTRUCTION OPERATIONS.
- NO OTHER UTILITY SERVICE/APPURTENANCES SHALL BE PLACED NEAR THE PROPERTY LINE, OR OTHER ASSIGNED LOCATION DESIGNATED FOR WATER AND WASTEWATER UTILITY SERVICE THAT WOULD INTERFERE WITH THE WATER AND WASTEWATER
- FOR PRESSURE TAPS, FURNISH, INSTALL AND AIR TEST THE SLEEVE AND VALVE. CONCRETE BLOCKING SHALLL BE PLACED BEHIND AND UNDER ALL TAP SLEEVES TWENTY-FOUR (24) HOURS PRIOR TO MAKING THE WET TAP.
- THRUST BLOCKING SHALL BE IN ACCORDANCE WITH THE SAN ANTONIO WATER SYSTEM
- ALL PUBLIC MAIN AND FIRE LINE PIPE SHALL BE PVC (AWWA C-900, DR-18). ALL DOMESTIC WATER PIPE SHALL BE C-900 PVC, DR-18.
- FOR WATERLINE MAINS AT WASTEWATER CROSSINGS WHERE WATER AND SEWER ARE PARALLEL AND SEPERATION OR DISTANCE CAN NOT BE ACHIEVED AS PER TAC 30, 317.13 USE EXTRA STIFF SDR 26 PVC (ASTM D 2241) WITH A PSI OF 150.
- EXTEND ALL EXISTING UTILITY MANHOLES, BOXES, COVERS, ETC. TO PROPOSED FINISH GRADE, UNLESS NOTED OTHERWISE.
- 10. FOR WATER LINE CROSSINGS WHERE THE MINIMUM 9 FOOT SEPARATION DISTANCE BETWEEN SEWER LINES AND WATER LINES/MAINS CANNOT BE MAINTAINED, THE INSTALLATION OF SEWER LINES SHALL BE IN STRICT ACCORDANCE WITH THE TEXAS COMMISSION ON ENVIRONMENTAL QUALITY RULES (31 TAC 217.13 APPENDIX E).
- 11. ALL PROPOSED ELECTRIC, PHONE, AND CABLE CONDUITS WILL BE PROVIDED WITH PULL
- 12. ALL ELECTRICAL WORK SHALL BE PER CITY OF SEGUIN STANDARDS.

EROSION AND SEDIMENTATION CONTROL NOTES

- THE CONTRACTOR SHALL INSTALL EROSION/SEDIMENTATION CONTROLS AND TREE/NATURAL AREA PROTECTIVE FENCING PRIOR TO ANY SITE PREPARATION WORK (CLEARING, GRUBBING, OR EXCAVATION).
- THE PLACEMENT OF EROSION/SEDIMENTATION CONTROLS SHALL BE IN ACCORDANCE WITH THE CITY OF SEGUIN'S CURRENT STANDARD AND THE APPROVED EROSION AND SEDIMENTATION CONTROL PLAN. CONTRACTOR SHALL BE REQUIRED TO PREPARE AND SUBMIT FOR CITY APPROVAL A STORM WATER POLLUTION PREVENTION PLAN (SWPPP) TO BE PREPARED BY A LICENSED ENGINEER AND INCORPORATE DETAILS INCLUDED IN THESE PLANS, AS APPROPRIATE.
- THE CONTRACTOR IS REQUIRED TO INSPECT THE CONTROLS AT WEEKLY INTERVALS AND AFTER SIGNIFICANT RAINFALL EVENTS TO ENSURE THEY ARE FUNCTIONING PROPERLY. THE PERSON(S) RESPONSIBLE FOR MAINTENANCE OF CONTROLS SHALL MMEDIATELY MAKE ANY NECESSARY REPAIRS TO DAMAGED AREAS. SILL ACCUMULATION AT CONTROLS MUST BE REMOVED WHEN THE DEPTH REACHES SIX (6)
- PRIOR TO FINAL ACCEPTANCE BY THE CITY, HAUL ROADS AND WATERWAY CROSSINGS CONSTRUCTED FOR TEMPORARY CONTRACTOR ACCESS MUST BE REMOVED FROM THE WATERWAY AND THE AREA RESTORED TO THE ORIGINAL GRADE AND REVEGETATED. ALL LAND CLEARING DEBRIS SHALL BY DISPOSED OF IN APPROVED SOIL DISPOSAL SITES.
- FIELD REVISIONS TO THE EROSION AND SEDIMENTATION CONTROL PLAN MAY BE REQUIRED BY THE CITY DURING THE COURSE OF CONSTRUCTION TO CORRECT CONTROL MADEQUACIES.
- PERMANENT EROSION CONTROL: ALL DISTURBED AREAS SHALL BE RESTORED AS
- NOTED BELOW:
 A MINIMUM OF FOUR INCHES OF TOPSOIL SHALL BE PLACED IN ALL DISTRUBED AREAS, DRAINAGE CHANNELS (EXCEPT ROCK), AND BETWEEN THE PAVEMENT AND RIGHT-OF-WAY LINE
- RIGHT-OF-WAY LINE.
 THE SEEDING FOR PERMANENT EROSION CONTROL SHALL BE APPLIED OVER
- THE SELDING FOR PERMANEN L EXCISION CONTROL SHALL BE APPLIED OVER
 AREAS DISTURBED BY CONSTRUCTION AS FOLLOWS:

 1. FROM SEPTEMBER 15 TO MARCH 1, SEEDING SHALL BE WITH A COMBINATION
 OF ONE (1) POUND PER 1000 SQUARE FEET OF UNHULLED BERMUDA AND
 SEVEN (7) POUNDS PER 1000 SQUARE FEET OF WINTER RYE WITH A PURITY
 OF 95% WITH 90% CERMINATION.
 2. FROM MARCH 2 TO SEPTEMBER 14, SEEDING SHALL BE WITH HULLED
- 2. FROM MARCH 2 TO SEPTEMBER 14, SELDING SHALL BE WITH HOLLED BERNUDA AT A RATE OF FOUR (4) POUNDS PER 1000 SQUARE FEET WITH A PURITY OF 95% WITH 85% GERMINATION.

 C. FERTILIZER SHALL HAVE AN ANALYSIS OF 15–15–15 AND SHALL BE APPLIED AT THE RATE OF 65 POUNDS PER ACRE.

 D. THE PLANTED AREA SHALL BE IRRIGATED OR SPRINKLED IN A MANNER THAT WILL NOT ERODE THE TOPSOIL BUT WILL SUFFICIENTLY SOAK THE SOIL TO A DEPTH OF SIX (6) INCHES. THE IRRIGATION SHALL OCCUPANT TENDAY INTERVALS DURING THE FIRST THE MONTHS PAURIEL OCCUPANT TENDAY INTERVALS DURING THE FIRST THE MONTHS PAURIEL OCCUPANT TENDAMENT. TWO MONTHS. RAINFALL OCCURRENCES OF 1/2 INCH OR MORE SHALL POSTPONE THE WATERING SCHEDULE FOR ONE WEEK.

 E. MULCH TYPE USED SHALL BE EITHER CELLULOSE FIBER, APPLIED AT A RATE OF 2000 POUNDS PER ACRE, OR WOOD FIBER MULCH APPLIED AT A RATE OF 2500 POUNDS PER ACRE.
- TEN AGN.

 RESTORATION SHALL BE ACCEPTABLE WHEN THE GRASS HAS GROWN AT LEAST 1-1/2 NCHES HIGH WITH 95% COVERAGE PROVIDED NO BARE SPOTS LARGER THAN 16

ALL CONSTRUCTED AND ALTERED DRAINAGE CHANNELS SHALL BE STABILIZED AND VEGETATED IMMEDIATELY AFTER FINAL GRADING.

TRAFFIC CONTROL NOTES

- THE CONTRACTOR WILL BE RESPONSIBLE FOR PROVIDING AND MAINTAINING ANY REQUIRED TRAFFIC CONTROL DEWICES DURING CONSTRUCTION IN ACCORDANCE WITH THE TEXAS DEPARTMENT OF TRANSPORTATION'S "TEXAS MANUAL ON UNIFORM CONTROL DEVICES FOR STREETS AND HIGHWAYS". ALL CONTROL DEVICES, LAYOUTS, AND MAINTENANCE SHALL BE INCIDENTAL TO THE COST ASSOCIATED WITH BORING THE HIGHWAYS, ROADS AND STREETS INDICATED ON THE CONTRACT DRAWNISS. WORK WITHIN TXDOT ROW SHALL CONFORM TO THE REQUIREMENTS OF THE UTILITY INSTALLATION PERMIT ISSUED BY THE TXDOT AND APPLICABLE TXDOT STANDARDS FOR UTILITY CONSTRUCTION AND TRAFFIC CONTROL
- UTILITY CONSTRUCTION AND TRAFFIC CONTROL



BS 123 12" WATER MAIN LOOP PHASE II & III

FROM HWY 90A AT PRESTON SOUTH TO FM 466 (EASTWOOD DR) EAST AND SOUTH TO COUNTRY SIDE BOULEVARD.

CITY OF SEGUIN, TEXAS

klotz (1) associates

7550 IH-10 West Northwest Center, Suite 300 San Antonio, TX 78229 Phone: (210) 736-0425 Fax: (210) 736-0405 sanantonio.office@klotz.com Texas PE Firm Reg. #F-929

SURVEY BENCHMARK:

BEARING BASED ON NAVD 1988 — TEXAS STATE PLANE COORDINATES, SOUTH CENTRAL ZONE.

- #1) TXDOT ALUMINUM MONUMENT LOCATED ON EAST COURT STREET (US 90A) 21.06' FROM THE NORTHWEST CORNER OF LOT 15 (VOL. 719, PG 1217) ELEVATION=523.05
- #2) A FOUND ½" REBAR WITH CAP "BA." ELEVATION=522.78'
- \$3) SANIATRY SEWER MANHOLE LOCATED 350' SOUTH OF COUNTRY LANE ON COUNTRYSIDE DRIVE.
- \$4) SANITARY SEWER MANHOLE LOCATED WEST ON COUNTRYSIDE ESTATES LOT 7 (VOL.5, PG 293B M.R).

REV	DESCRIPTION	ΒY	DATE

GENERAL NOTES



08/01/2014

CITY OF SEGUIN 123 BYPASS WATER LOOP

Drawn By BAL	Checked By LAC					
	Date AUGUST 2014					
DWG No C1.0	Sheet 1 Of 18					

ITEM NO.

100

101

ITEM DESCRIPTION

PREPARING RIGHT-OF-WAY

MOBILIZATION

QUANTITY

UNIT

LS

LS



BS 123 12" WATER MAIN LOOP PHASE II & III

FROM HWY 90A AT PRESTON SOUTH TO FM 466 (EASTWOOD DR) EAST AND SOUTH TO COUNTRY SIDE BOULEVARD.

CITY OF SEGUIN, TEXAS

klotz (i) associates

7550 IH-10 West Northwest Center, Suite 300 San Antonio, TX 78229 Phone: (210) 736-0425 Fax: (210) 736-0405 sanantonio.office@klotz.com Texas PE Firm Reg. #F-929

SURVEY BENCHMARK:

BEARING BASED ON NAVD 1988 - TEXAS STATE PLANE COORDINATES, SOUTH CENTRAL ZONE.

- #1) TXDOT ALUMINUM MONUMENT LOCATED ON EAST COURT STREET (US 90A) 21.06' FROM THE NORTH-WEST CORNER OF LOT 15 (VOL. 719, PG 1217) ELEVATION=523.05
- #2) A FOUND ½" REBAR WITH CAP "BA." ELEVATION=522.78"
- #3) SANIATRY SEWER MANHOLE LOCATED 350' SOUTH OF COUNTRY LANE ON COUNTRYSIDE DRIVE. ELEVATION=531.26'
- #4) SANITARY SEWER MANHOLE LOCATED WEST ON COUNTRYSIDE ESTATES LOT 7 (VOL.5, PG 293B M.R). ELEVATION=533.10'

REV	DESCRIPTION	BY	DATE

12" WATER MAIN
QUANTITIES



08/01/2014

CITY OF SEGUIN 123 BYPASS WATER LOOP

Drawn By	BAL	Checked By LAC
Scale		Date AUGUST 2014
DWG No	C2.0	Sheet 2 Of 18

CALL THE TEXAS WIDE STATE ONE CALL LOCATOR AT 1-800-344-8377. 48 HOURS BEFORE ANY CONSTRUCTION.

DUE TO FEDERAL REGULATION TITLE 49, PART 192.181, CENTERPOINT ENERGY MUST MAINTAIN ACCESS TO GAS VALVES AT ALL TIMES. THE CONTRACTORY FOREMAN MUST PROTECT AND WORK AROUND ANY GAS VALVES THAT ARE IN THE PROJECT AREA.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING OVERHEAD AND UNDERGROUND ELECTRIC FACILITIES IF ADJACENT TO WORK AREA.

THE EXISTENCE AND LOCATION OF UNDERGROUND CABLE INDICATED ON THE PLANS ARE TAKEN FROM THE BEST RECORDS AVAILABLE AND ARE NOT GUARANTEED TO BE ACCURATE. CONTRACTOR/FOREMAN IS RESPONSIBLE FOR MAINTAINING AND PROTECTING THE INTEGRITY OF POWER POLES AND UNDERGROUND ELECTRIC CABLES DURING (NSPI) CONSTRUCTION. 48 HOURS BEFORE BEGINNING ANY EXCAVATION CALL THE TEXAS WIDE STATE ONE CALL LOCATOR AT 1-800-344-8377. CONTRACTOR TO PROTECT AND SUPPORT TELEPHONE COMPANY PLANT DURING CONTRUCTION.

TRENCH EXCAVATION SAFTEY PROTECTION

TRENCH EXCAVATION PROTECTION SHALL BE ACCOMPLISHED AS REQUIRED BY THE PROVISIONS OF PART 1926, SUBPART P-EXCAVATION, TRENCHING, AND SHORING OF THE OCCUPATIONAL SAFETY AND HEALTH'S STANDARDS AND INTERPRETATIONS. THE CONTRACTOR/FOREMAN SHALL ALSO COMPLY WITH 550, TRENCH EXCAVATION PROTECTION, SAN ANTONIO WATER SYSTEM SPECIFICATIONS FOR WATER CONSTRUCTION.



BS 123 12" WATER MAIN LOOP PHASE II & III

FROM HWY 90A AT PRESTON SOUTH TO FM 466 (EASTWOOD DR) EAST AND SOUTH TO COUNTRY SIDE BOULEVARD.

CITY OF SEGUIN, TEXAS

klotz (1) associates

7550 IH-10 West Northwest Center, Suite 300 San Antonio, TX 78229 Phone: (210) 736-0425 Fax: (210) 736-0405 sanantonio.6fice@klotz.com Texas PE Firm Reg. #F-929

SURVEY BENCHMARK:

BEARING BASED ON NAVD 1988 — TEXAS STATE PLANE COORDINATES, SOUTH CENTRAL ZONE.

- #1) TXDOT ALUMINUM MONUMENT LOCATED ON EAST COURT STREET (US 90A) 21.06' FROM THE NORTHWEST CORNER OF LOT 15 (VOL. 719, PG 1217) ELEVATION=523.05
- #2) A FOUND ½" REBAR WITH CAP "BA." ELEVATION=522.78'
- #3) SANIATRY SEWER MANHOLE LOCATED 350' SOUTH OF COUNTRY LANE ON COUNTRYSIDE DRIVE. ELEVATION=531.26'
- #4) SANITARY SEWER MANHOLE LOCATED WEST ON COUNTRYSIDE ESTATES LOT 7 (VOL.5, PG 293B M.R). ELEVATION=533.10'

REV	DESCRIPTION	BA	DATE


OVERALL
PROJECT LAYOUT



08/01/2014

CITY OF SEGUIN 123 BYPASS WATER LOOP

Drawn By BAL	Checked By LAC
Scale	Date AUGUST 2014
DWG No C3.0	Sheet 3 Of 18





WORK SPACE NEAR SHOULDER

Conventional Roads

50 mph less

♡Ⅰ☆





TCP (2-1c)

WORK VEHICLES ON SHOULDER Conventional Roads

LEGEND										
	Type 3 Barricade		Channelizing Devices							
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)							
	Trailer Mounted Flashing Arrow Board	(M	Portable Changeable Message Sign (PCMS)							
-	Sign	∿	Traffic Flow							
\Diamond	Flag	ПО	Flagger							

Speed	Formula	Formula Desirable Taper Lengths X X			Spacir Channe		Minimum Sign Spacing "X"	Suggested Longitudinal Buffer Space	
*		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	Distance	"B"	
30	WS ²	150′	165′	180′	30′	60′	120′	90′	
35	$L = \frac{WS}{60}$	205′	225′	245′	35′	70′	160′	120′	
40	80	265′	295′	320′	40′	80′	240′	155′	
45		450′	495′	540′	45′	90′	320′	195′	
50		500′	550′	600′	50′	100′	400′	240′	
55	L=WS	550′	605′	660′	55′	110′	500′	295′	
60	- "3	600′	660′	720′	60′	120'	600′	350′	
65		650′	715′	780′	65′	130′	700′	410′	
70		700′	770′	840′	70′	140′	800′	475′	
75		750′	825′	900′	75′	150′	900′	540′	

X Conventional Roads Only

** Taper lengths have been rounded off.

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE									
MOBILE	MOBILE SHORT SHORT TERM INTERMEDIATE DURATION STATIONARY TERM STATIONARY								
	1	✓	√	1					

GENERAL NOTES

1. Flags attached to signs where shown, are REQUIRED.

substituted for the Shadow Vehicle and TMA.

2. All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated in the plans, or for routine maintenance work, when approved by the Engineer.

3. Stockpiled material should be placed a minimum of 30 feet from

nearest traveled way.

4. Shadow Vehicle with TMA and high intensity rotating, flashing, oscillating or strobe lights. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be

5. Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space. 6. See TCP(5-1) for shoulder work on divided highways, expressways and

freeways.

7. Inactive work vehicles or other equipment should be parked near the right-of-way line and not parked on the paved shoulder.

8. CW21-5 "SHOULDER WORK" signs may be used in place of CW21-1D "ROAD WORK AHEAD" signs for shoulder work on conventional roadways.


For construction or maintenance contract work, specific project requirements for shadow vehicles can be found in the project GENERAL NOTES for Item 502, Barricades, Signs and Traffic Handling.


Texas Department of Transportation Traffic Operations Division

TRAFFIC CONTROL PLAN CONVENTIONAL ROAD SHOULDER WORK

TCP(2-1)-12

© TxDOT December 1985	DN: TXDOT		CK: TXDOT DW:		TXDQT	CK: TXDOT	
REVISIONS	CONT	SECT	JOB		ні	HIGHWAY	
2-94 2-12 8-95							
1-97	DIST	COUNTY			SHEET NO.		
4-98						C4.0	
1.6.1							





LEGEND										
	Type 3 Barricade		Channelizing Devices							
	Heavy Work Vehicle		Truck Mounted Attenuator (TMA)							
	Trailer Mounted Flashing Arrow Board		Portable Changeable Message Sign (PCMS)							
þ	Sign	∜	Traffic Flow							
\Diamond	Flag	4	Flagger							

Speed	Minimum Desirable Formula Taper Lengths X X		Suggested Maximum Spacing of Channelizing Devices		Minimum Sign Spacing "X"	Suggested Longitudinal Buffer Space	Stopping Sight Distance		
*		10' Offset	11' Offset	12' Offset	On a Taper	On a Tangent	Distance	"B"	
30	2	150′	165′	180′	30′	60′	120′	90′	200′
35	$L = \frac{WS^2}{60}$	205′	225′	245'	35′	70′	160′	120′	250′
40	80	265′	295′	320′	40′	80′	240′	155′	305′
45		450′	495′	540′	45′	90′	320′	195′	360′
50		500′	550′	600′	50′	100′	400′	240′	425′
55	L=WS	550′	605′	660′	55′	110′	500′	295′	495′
60	L-#3	600′	660′	720′	60′	120′	600′	350′	570′
65		650′	715′	780′	65′	130′	700′	410′	645′
70		700′	770′	840′	70′	140′	800′	475′	730′
75		750′	825′	900′	75′	150′	900′	540′	820′

* Conventional Roads Only

** Taper lengths have been rounded off.

L=Length of Taper(FT) W=Width of Offset(FT) S=Posted Speed(MPH)

TYPICAL USAGE						
MOBILE	SHORT DURATION	SHORT TERM STATIONARY	INTERMEDIATE TERM STATIONARY	LONG TERM STATIONARY		
	1	1	1			

GENERAL NOTES

1. Flags attached to signs where shown, are REQUIRED.

- 2. All traffic control devices illustrated are REQUIRED, except those denoted with the triangle symbol may be omitted when stated elsewhere in the plans, or for routine maintenance work, when approved by the Engineer.
- The CW3-4 "BE PREPARED TO STOP" sign may be installed after the CW20-4 "ONE LANE ROAD XXX FT" sign, but proper sign spacing shall be maintained.
 Flaggers should use two-way radios or other methods of communication to control traffic.

5. Length of work space should be based on the ability of flaggers to communicate.

- 6. A Shadow Vehicle with a TMA should be used anytime it can be positioned 30 to 100 feet in advance of the area of crew exposure without adversely affecting the performance or quality of the work. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA. If workers are no longer present but road or work conditions require the traffic control to remain in place, Type 3 Barricades or other channelizing devices may be substituted for the Shadow Vehicle and TMA.
- 7. Additional Shadow Vehicles with TMAs may be positioned off the paved surface, next to those shown in order to protect a wider work space.

TCP (2-2a)

- 8. The R1-2 "YIELD" sign traffic control may be used on projects with approaches that have adequate sight distance. For projects in urban greas, work space should be no longer than one half city block. In rural areas, roadways with less than 2000 ADT, work space should be no longer than 400 feet.
- 9. The R1-2aP "YIELD TO ONCOMING TRAFFIC" sign shall be placed on a support at a 7 foot minimum

TCP (2-2b)

- 10. Channelizing devices on the center line may be omitted when a pilot car is leading traffic and approved by the Engineer.
- 11. If the work space is located near a horizontal or vertical curve, the buffer distances should be increased in order to maintain stopping sight distance to the flagger and a queue of stopped vehicles.

162

12.Flaggers should use 24" STOP/SLOW paddles to control traffic. Flags should be limited to emergency situtations.


> For construction or maintenance contract work, specific project requirements for shadow vehicles can be found in the project GENERAL NOTES for Item 502, Barricades, Signs and Traffic Handling.

Texas Department of Transportation Traffic Operations Division

TRAFFIC CONTROL PLAN ONE-LANE TWO-WAY TRAFFIC CONTROL

TCP (2-2) -12

© TxDOT December 1985	DN: TXE	тот	CK: TXDOT	DW:	TXDOT	CK: TXDOT
REVISIONS	CONT	SECT	JOB		H:	GHWAY
8-95 2-12 1-97						
4-98	DIST		COUNTY			SHEET NO.
3-03						C5.0



SECTION A-A

GENERAL NOTES

1. The guidelines shown hereon are suggestions only and may be modified by the Engineer.

PLAN SHEET LEGEND


Sediment Control Fence -

SEDIMENT CONTROL FENCE USAGE GUIDELINES


A sediment control fence may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A 2 year storm frequency may be used to calculate the flow rate to be filtered.

Sediment control fence should be sized to filter a max. flow through rate of 100 GPM/FT 2 . Sediment control fence is not recommended to control erosion from a drainage area larger than 2 acres.


Galv. Hinge joint knot woven mesh (12.5 Ga. Min.) requires a minimum of five horizontal wires spaced at a max.12 inches apart and all vertical wires spaced at a max. 12 inches apart.




Hinge Joint Knot Woven Mesh (Option)



_____(SCF)____



PLAN VIEW



PROFILE VIEW

PLANS SHEET LEGEND

Baled Hay — BH)

BALED HAY USAGE GUIDELINES


A Baled Hay installation may be constructed near the downstream perimeter of a disturbed area along a contour to intercept sediment from overland runoff. A two year storm frequency may be used to calculate the flow rate to be filtered. The installation should be sized to filter a maximum flow thru rate of 5 $\mathsf{GPM}/\mathsf{FT}^2$ of cross sectional area. Baled hay may be used at the following locations:

- 1. Where the runoff approaching the baled hay flows over disturbed soil for less than 100'. If the slope of the disturbed soil exceeds 10%, the length of slope upstream the baled hay should be less than 50'.
- 2. Where the installation will be required for less than 3 months.
- 3. Where the contributing drainage area is less than $\frac{1}{2}$ acre.


For Baled Hay installations in small ditches, the additional following considerations apply:

- 1. The ditch sideslopes should be graded as flat as possible to maximize the drainage flowrate thru the hay.
- 2. The ditch should be graded large enough to contain the overtopping drainage when sediment has filled to the top of the baled hay.

Bales should be replaced usually every 2 months or more often during wet weather when loss of structural integrity is accelerated.




SECTION B-B




GENERAL NOTES


- 1. Hay bales shall be a minimum of 30" in length and weigh a minimum of 50 Lbs.
- Hay bales shall be bound by either wire or nylon or polypropylene string. The bales shall be composed entirely of vegetative matter.
- 3. Hay bales shall be embedded in the soil a minimum of 4" and where possible $\frac{1}{2}$ the height of the bale.
- Hay bales shall be placed in a row with ends tightly abutting the adjacent bales. The bales shall be placed with bindings parallel to the around.
- Hay bales shall be securely anchored in place with $\frac{3}{8}$ " Dia. rebar or 2" x 2" wood stakes, driven through the bales. The first stake shall be angled towards the previously laid bale to force the bales together.
- 6. The guidelines shown hereon are suggestions only and may be modified by the Engineer.



EC(1)-09

ILE: ec109.dgn	DN: Tx[)OT	CK: AM	DW: TV	ck: BD
C TxDOT June 1993	CONT	SECT	JOB		HIGHWAY
REVISIONS					
	DIST		COUNTY		SHEET NO.
					C6.0






PROFILE


CONSTRUCTION EXIT (TYPE 1)

GENERAL NOTES

- 1. The length of the type 1 construction exit shall be as indicated on the plans, but not less than 50'.
- 2. The coarse aggregate should be open graded with a size of 4" to 8".
- 3. The approach transitions should be no steeper than 6:1 and constructed as directed by the Engineer.
- 4. The construction exit foundation course shall be flexible base. bituminous concrete, portland cement concrete or other material as approved by the Engineer.
- 5. The construction exit shall be graded to allow drainage to a sediment trapping device.
- 6. The guidelines shown hereon are suggestions only and may be modified by the Engineer.




PLAN




PROFILE

CONSTRUCTION EXIT (TYPE 2)

- as approved by the Engineer.
- 3. The treated timber planks shall be #2 grade min., and should be free from large and loose knots.
- 4. The approach transitions shall be no steeper than 6:1 and
- The construction exit foundation course shall be flexible base, bituminous concrete, portland cement concrete or other material as approved by the Engineer.
- 6. The construction exit should be graded to allow drainage to a
- 7. The guidelines shown hereon are suggestions only and may



<u>PLAN</u>




SECTION A-A

CONSTRUCTION EXIT (TYPE 3)

GENERAL NOTES

- 1. The length of the type 3 construction exit shall be as shown on the plans, or as directed by the Engineer.
- 2. The type 3 construction exit may be constructed from open graded crushed stone with a size of two to four inches spread a min. of 4" thick to the limits shown on the plans.
- 3. The treated timber planks shall be #2 grade min., and should be free from large and loose knots.
- 4. The guidelines shown hereon are suggestions only and may be modified by the Engineer.




EC(3) - 93

ILE: ec393.dgn	DN: Tx[TOC	ск: НЕ Ј	DW:	BD		CK:
TxDOT June 1993	CONT	SECT	JOB			HIG	YAWH
REVISIONS							
	DIST		COUNTY			S	HEET NO.
							C7.0

GENERAL NOTES

- The length of the type 2 construction exit shall be as indicated on the plans, but not less than 50° .
- 2. The treated timber planks shall be attached to the railroad ties with $1/2\,\mathrm{m}\,\mathrm{x}$ 6" min. lag bolts. Other fasteners may be used
- constructed as directed by the Engineer.
- sediment trapping device.
- be modified by the Engineer.



Dike in cut operations Dike in fill operations Existing public travelway Original ground Embankment area

Top width 2 ft Minimum Height from upslope toe 18 In Minimum Existing or graded ground

TYPICAL DIKE CONFIGURATION

Soil used in dike construction shall be machine compacted.

modified with prior approval of the

3. Side slopes within the safety clear zone

of a roadway shall be 6:1 or flatter. 4. Grading shall be shown elsewhere in the plans or as directed by the Engineer.

2. Top width and height of dike may be

5. The Engineer reserves the right to modify the dimensions shown for the dike dependent on runoff volume

6. Dikes that are in place for more than 14 calendar days should be stabilized

7. The guidelines shown hereon are suggestions only and may be modified by the Engineer.

to prevent sediment runoff.

GENERAL NOTES:

Engineer.

characteristics.

PERIMETER DIKE

Dike ---(D)---

DIVERSION DIKE

Dike ---(D)----

Daily embankment placement See typical dike configuration Dike to be incorporated into next embankment lift.

EMBANKMENT SECTION - DIVERSION DIKE

Dike →D

See typical dike configuration Construction Zone _ Discharge to perimeter diversion structure, sediment trap, or stabilized area.

INTERCEPTOR DIKE

A dike may be used to intercept runoff and divert it around unstabilized areas or to divert sediment laden runoff to an erosion control device (sediment basin or trap, rock filter

The drainage area contributing runoff to a dike should not exceed 5 acres. The spacing of dikes should be as follows:

Slope of disturbed areas above dike	greater than 10%	5 - 10%	less than 5%
Maximum distance	100′	200′	300′

Intercepted runoff flowing along a dike should outlet to a stabilized area (vegetation, rock, etc.).

DIKE USAGE GUIDELINES

(EARTHWORK FOR EROSION CONTROL) EC(4) - 93


Texas Department of Transportation

TEMPORARY EROSION, SEDIMENT AND WATER

POLLUTION CONTROL MEASURES DIKES

ILE: ec493.dgn DN: TxDOT CK: HEJ DW: BD CK: © TxDOT June 1993 DIST SHEET NO.

PLANS SHEET LEGEND




See perimeter, diversion, or interceptor dike details Discharge to level spreader or sediment trapping device

1 ft minimum See Note 2 Flow In the second of the secon

TYPICAL SWALE CONFIGURATION

PERIMETER SWALE





DIVERSION DIKE WITH SWALE

DIVERSION SWALE

GENERAL NOTES:

- Dimensions of swale may be modified with prior approval of the Engineer.
- 2. Side slopes within the safety clear zone of a roadway shall be 6:1 or flatter.
- Grading shall be shown elsewhere on the plans or as directed by the Engineer.
- 4. The Engineer reserves the right to modify the dimensions shown for the swale dependent on runoff volume characteristics.
- Swales that are in place for more than 14 calender days should be stabilized through seeding or other measures to control sediment runoff.
- 6. The guidelines shown hereon are suggestions only and may be modified by the Engineer.

See typical swale configuration Flow Disturbed area or alternate sediment trapping device

INTERCEPTOR SWALE

PLANS SHEET LEGEND

Swale — S — Dike — D —

SWALE AND DIKE/SWALE USAGE GUIDELINES

A swale or dike/swale may be used to intercept runoff and divert it around unstabilized areas or to divert sediment laden runoff to an erosion control device (sediment basin or trap, rock filter dam, etc.).

The drainage area contributing runoff to a swale or dike/swale should not exceed 5 acres. The spacing of swales and dike/swales should be as follows:

Slope of disturbed greater less than 10% 5 - 10% than 5%

Maximum distance 100′ 200′ 300′ between dikes

Intercepted runoff flowing in a swale or dike/swale should outlet to a stabilized area (vegetation, rock, etc.).




SEDIMENT AND WATER
POLLUTION CONTROL MEASURES
SWALES
(EARTHWORK FOR EROSION CONTROL)

EC(5)-93

ILE: ec593.dgn	DN: Tx[)OT	ck: HEJ	DW:	BD	1	CK:
TxDOT May 1993	CONT	SECT	JOB			HIGH	IWAY
REVISIONS							
	DIST		COUNTY			SH	HEET NO.
						(C9.0
						(C9.0

DATE: FILE:



2. The device must have filter fabric material that will allow water flow but stop sediment. It will extend from bottom up vertical plane a minimum of 2" and full width of horizontal bottom plane. The filter fabric shall be attached to the back of the plastic mesh. It shall not cover more than 1/3 of the height of the vertical plane opening to allow overflow in larger strom events to prevent flooding of travel lanes. Filter Fabric Physical Requirements Table

Apparent Opening Size (AOS)	400 to 600 microns		
Percent Open Area (POA)	>10%		
	130 gallons per SF per minute with clean water or greater.		

- 3. Place with horizontal plane pointing away from curb.
- 4. For high openings, the device or attachment should extend above opening.
- 5. For long curb openings, overlap the segments 6". Tie together with 4 zip ties in 4 places, 2 at the top and 2 at the bottom.
- 6. Install gravel, not sand, bags at each end, at overlaps and in the middle of each section. Use 1/3 full bags for low profile and best traffic avoidance.
- 7. Use bags that will have long-term resistance to UV exposure.
- 8. Sediment should be removed and device cleaned when sediment reaches 1" in depth.


© Texas Department of Transportation


DALLAS DISTRICT STANDARD
TEMPORARY EROSION,
SEDIMENT AND WATER
POLLUTION CONTROL MEASURES


CURB INLET SEDIMENT PROTECTION


FED. RD. DIV. NO.		SHEET NUMBER			
18				C10.0	
STATE	DISTRICT				
TEXAS	DALLAS				
CONTROL	SECTION	SECTION	NUMBER		
0000	00	000 IH/SH/FM			


REVISED ON 9/10/08




























BS 123 12" WATER MAIN LOOP PHASE II & III

FROM HWY 90A AT PRESTON SOUTH TO FM 466 (EASTWOOD DR) EAST AND SOUTH TO COUNTRY SIDE BOULEVARD.

CITY OF SEGUIN, TEXAS

klotz (1) associates

7550 IH-10 West Northwest Center, Suite 300 San Antonio, TX 78229 Phone: (210) 736-0425 Fax: (210) 736-0405 sanantonio.office@klotz.com Texas PE Firm Reg. #F-929

SURVEY BENCHMARK:

BEARING BASED ON NAVD 1988 - TEXAS STATE PLANE COORDINATES, SOUTH CENTRAL ZONE.

- #1) TXDOT ALUMINUM MONUMENT LOCATED ON EAST COURT STREET (US 90A) 21.06' FROM THE NORTH-WEST CORNER OF LOT 15 (VOL. 719, PG 1217) ELEVATION=523.05
- #2) A FOUND ½" REBAR WITH CAP "BA." ELEVATION=522.78'
- #3) SANIATRY SEWER MANHOLE LOCATED 350' SOUTH OF COUNTRY LANE ON COUNTRYSIDE DRIVE. ELEVATION=531.26'
- #4) SANITARY SEWER MANHOLE LOCATED WEST ON COUNTRYSIDE ESTATES LOT 7 (VOL.5, PG 293B M.R). ELEVATION=533.10'

REV	DESCRIPTION	BY	DATE
	DEGGIIII IIGII		D/11.E


WATER LINE CONSTRUCTION **DETAILS** SHEET 1 OF 5





08/01/2014


CITY OF SEGUIN **123 BYPASS WATER LOOP**


Drawn By	BAL	Checked By LAC
Scale		Date July 2013
DWG No	C15.0	Sheet 15 Of 18

















TABI	E 847-1		
CHLORINE DOSAGE			
Ounces Per Foot; Diameter of Pipe in Inches	To Obtain 50 ppm Chlorine Dosage		
6	0.0138		
8	0.0233		
10	1.0		
12	0.0523		
14	0.0708		
16	0.0934		
18	0.1175		
20	0.1455		
24	0.208		
30	0.327		
36	0.469		
42	0.637		
48	0.0833		
54	1.0575		



BS 123 12" WATER MAIN LOOP PHASE II & III

FROM HWY 90A AT PRESTON SOUTH TO FM 466 (EASTWOOD DR) EAST AND SOUTH TO COUNTRY SIDE BOULEVARD.

CITY OF SEGUIN, TEXAS

klotz 📢 associates

7550 IH-10 West Northwest Center, Suite 300 San Antonio, TX 78229 Phone: (210) 736-0425 Fax: (210) 736-0405 sanantonio-office@klotz.com Texas PE Firm Reg. #F-929

SURVEY BENCHMARK:

BEARING BASED ON NAVD 1988 — TEXAS STATE PLANE COORDINATES, SOUTH CENTRAL ZONE.

- #1) TXDOT ALUMINUM MONUMENT LOCATED ON EAST COURT STREET (US 90A) 21.06' FROM THE NORTH-WEST CORNER OF LOT 15 (VOL. 719, PG 1217) ELEVATION=523.05
- #2) A FOUND ½" REBAR WITH CAP "BA." ELEVATION=522.78'
- #3) SANIATRY SEWER MANHOLE LOCATED 350' SOUTH OF COUNTRY LANE ON COUNTRYSIDE DRIVE. ELEVATION=531.26'
- #4) SANITARY SEWER MANHOLE LOCATED WEST ON COUNTRYSIDE ESTATES LOT 7 (VOL.5, PG 293B M.R). ELEVATION=533.10'


REV	DESCRIPTION	BY	DATE

WATER LINE CONSTRUCTION **DETAILS** SHEET 2 OF 4



CITY OF SEGUIN **123 BYPASS WATER LOOP**

Drawn By BAL	Checked By LAC
Scale	Date July 2013
DWG No C16.C	Sheet 16 ^{Of} 18





UNION PACIFIC RALROAD CROSSING CASING REQUIREMENT			
Nom.Dia. Steel	Steel Fipe	Pipe Weight	
Conduit (Inches)	Thickness (Inches)	(Lbs/Ft.)	
18	0.375	70.59	
24	0.438	110.22	
30	0.50	157.53	
36	0.562	212.70	
42	0.625	276.18	
48	0.625	316.53	


WATER MAINS IN CONDUIT			
Water Nain Size (Inches)	Nom.Dia. RCP* Or Stiel (Inches)	Steel Pipe Thickness (Inches)	Pipe Weight (Lbs/Ft.)
6	18	0.375	7059
8	24	0.375	9432
12	24	0.375	9432
16	30	0.375	118.35
20	36	0.438	16619
24	42	0.438	19402
30	48	0.50	25902
36	54	0.50	29107


* Class I or IV Tongue and Groove for nor-railroad applications


PROPERTY OF	Commence Commence of the Comme	APPROVED	REVSED
SAN ANTONIO WATER SYSTEM	INSTALLATION OF PIPE	March 2008	
SAN ANTONIO WATER STSTEM	IN CONDUIT	DD-856-01	SHEET 1 OF 2













BS 123 12" WATER MAIN LOOP PHASE II & III

FROM HWY 90A AT PRESTON SOUTH TO FM 466 (EASTWOOD DR) EAST AND SOUTH TO COUNTRY SIDE BOULEVARD.

CITY OF SEGUIN, TEXAS

klotz (3) associates

7550 IH-10 West Northwest Center, Suite 300 San Antonio, TX 78229 Phone: (210) 736-0425 Fax: (210) 736-0405 sanantonio-office@klotz.com Texas PE Firm Reg. #F-929

SURVEY BENCHMARK:

BEARING BASED ON NAVD 1988 - TEXAS STATE PLANE COORDINATES, SOUTH CENTRAL ZONE.

- #1) TXDOT ALUMINUM MONUMENT LOCATED ON EAST COURT STREET (US 90A) 21.06' FROM THE NORTH-WEST CORNER OF LOT 15 (VOL. 719, PG 1217) ELEVATION=523.05
- #2) A FOUND ½" REBAR WITH CAP "BA." ELEVATION=522.78'
- #3) SANIATRY SEWER MANHOLE LOCATED 350' SOUTH OF COUNTRY LANE ON COUNTRYSIDE DRIVE. ELEVATION=531.26'
- #4) SANITARY SEWER MANHOLE LOCATED WEST ON COUNTRYSIDE ESTATES LOT 7 (VOL.5, PG 293B M.R). ELEVATION=533.10'


RFV	DESCRIPTION	RY	DATE
	DESCRIPTION		571.12


WATER LINE CONSTRUCTION **DETAILS** SHEET 4 OF 4




CITY OF SEGUIN **123 BYPASS WATER LOOP**

Drawn By	BAL	Checked By LAC
Scale		Date July 2013
DWG No	C17.0	Sheet 17 Of 18









BS 123 12" WATER MAIN LOOP PHASE II & III

FROM HWY 90A AT PRESTON SOUTH TO FM 466 (EASTWOOD DR) EAST AND SOUTH TO COUNTRY SIDE BOULEVARD.

CITY OF SEGUIN, TEXAS

klotz 📢 associates

7550 IH-10 West Northwest Center, Suite 300 San Antonio, TX 78229 Phone: (210) 736-0425 Fax: (210) 736-0405 sanantonio.office@klotz.com Texas PE Firm Reg. #F-929

SURVEY BENCHMARK:

BEARING BASED ON NAVD 1988 — TEXAS STATE PLANE COORDINATES, SOUTH CENTRAL ZONE.

- #1) TXDOT ALUMINUM MONUMENT LOCATED ON EAST COURT STREET (US 90A) 21.06 FROM THE NORTHWEST CORNER OF LOT 15 (VOL. 719, PG 1217) ELEVATION=523.05
- #2) A FOUND ½" REBAR WITH CAP "BA." ELEVATION=522.78'
- #3) SANIATRY SEWER MANHOLE LOCATED 350' SOUTH OF COUNTRY LANE ON COUNTRYSIDE DRIVE. ELEVATION=531.26'
- #4) SANITARY SEWER MANHOLE LOCATED WEST ON COUNTRYSIDE ESTATES LOT 7 (VOL.5, PG 293B M.R). ELEVATION=533.10'

REV	DESCRIPTION	BY	DATE

WATER LINE CONSTRUCTION DETAILS SHEET 4 OF 4



08/01/2014

CITY OF SEGUIN 123 BYPASS WATER LOOP

Klotz Project No 0131.001.001

Drawn By	BAL	Checked By LAC
Scale		Date July 2013
DWG No	C18.0	Sheet 18 ^{Of} 18



SPECIFICATIONS: PVC Meter Box.

Approximate Size: 14" Wide x 16" Long x 12" Deep
Lid to be AMR Compatible. To be used with Adara Star
Fixed Network System (Hexagram).

Lid Shall Have S Lock and S Bolt Locking System



Approved Vendor ACT Pipe Big Country Ferguson GA Powers HD Supply Waterworks Morrison Supply Municipal Waterworks

Approved Mig.

Part#

DFW

1324C-1SA

573 085 00004

07/05/13