



REINFORCING BAR DETAIL

NOTE:

ALTERNATE #4 BARS PLACED ON CHAIRS AT MIDDEPTH OF SLAB TO BE CONTINUOUS ACROSS EXPANSION JOINT. BREAK BOND 6" ON EACH SIDE OF EXPANSION JOINT.

CONCRETE VALLEY GUTTER



THE CITY OF  
SEGWIN

DATE ISSUED:	JUNE 1, 2013		
REV	DATE	BY	

TITLE	
CONCRETE VALLEY GUTTER SHEET 1 OF 2	
SCALE:	DRAWING No.
N.T.S.	RDWY-7.1