



INLET SECTION VIEW  
FINAL PHASE

**MATERIAL SPECIFICATION:**

- A. WIRE FABRIC – CHAIN LINK MESH
- B. FILTER MATERIAL – EXCELSIOR MATERIAL

**MAINTENANCE REQUIREMENTS:**

WITHIN FORTY EIGHT (48) HOURS OF POURING THE BLOCKOUT AND TOP, PLACE MESH ROLL WITH 2" OPENING OVER ALL CURB AND GRATE OPENINGS SO THAT AT LEAST 2 FEET OF ROLL EXTENDS BEYOND EACH END OF THE GUTTER OPENING. IF THE SEDIMENT FILTER BECOMES CLOGGED WITH DEBRIS SO THAT IT NO LONGER ADEQUATELY PERFORMS ITS FUNCTION, REMOVE THE ROLL, CLEAN IT AND/OR REPLACE IT. MAKE WEEKLY INSPECTIONS OF THESE SEDIMENT FILTERS FOR CONFORMANCE TO THESE CONDITIONS. PARTICULARLY INSPECT ALL INLETS AFTER EACH RAIN. COMPLETELY REMOVE ALL SEDIMENT FILTERS UPON ESTABLISHMENT OF GRASS AND FINAL STABILIZATION OF CONSTRUCTION SITE. DO NOT USE A SEDIMENT FILTER TO CONTROL EROSION AROUND "Y" INLETS. UTILIZE SEDIMENT FENCES.



THE CITY OF  
**SEGUIN**

DATE ISSUED: JUNE 1, 2013		TITLE	
REV	DATE	BY	STORM SEWER INLET PROTECTION
SCALE: N.T.S.		DRAWING No. EC-5	